BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64
EE/YNK/BBMP/E-PMT/09/2017-18 Dated: 31-08-2

APPROVED TENDER SCHEDULE –'B'

Item No: 01

Name of Work:-:Improvements and interior works to Karagamantapa and improvements to Kalyani Surrounding areas at Yelahanka kalyani in ward no:01

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri B P MAHESH	
				Rate	Rate in Words
1	KSRB 2-2.1 : Earth work excavation for foundation of buildings, culverts water supply, sanitary line and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5m, in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m, after breaking of clods complete as per specifications, specification, No, KBS 2.1(a) / 2.3.5, No.5/Item No. 2.3)	Cum	184.70	210.00	Rupees Two Hundred Ten Only
2	KSRRB M100-1 Loading and Unloading of Stone Boulder / Stone aggregate /sand/kaner/ Moorum KSRRB M100-1 Placing tipper at loading point, loading with front end loader, dumping, turning for return trip, excluding time for haulage and return trip complete as per specifications MORTH -100/ Chapter 1 (Page No.133/ Item No.17.1)	Cum	184.70	150.00	Rupees One Hundred Fifty Only
3	KSRB 5.1-2 : Providing and constructing granite / trap / basalt rubble stone masonry in foundation with cement mortar 1:6 (Uncoursed), bond stones at 2m. apart in each course including cost of materials, labour, curing complete as per specifications.KBS 5.1.12 (Page No.23/ Item No.5.3)	Cum	10.37	3600.00	Rupees Three Thousand Six Hundred Only
4	KSRRB M2100-10. Plain cement concrete M10 with OPC cement @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @ 0.84cum and fine aggregates @ 0.56cum in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14days complete as per specifications. MORTH Specification No.2100(P.No.218 & It.No.27.18)	Cum	11.33	6100.00	Rupees Six Thousand One Hundred Only
5	KSRRB M2200-5.14 : Design mix M30 with OPC cement @ 360kgs , with 20mm and down size graded granite metal,coarseaggregated @ 0.69cum ,and fine aggregated @ 0.46cum, with superplastisiser @ 3lts confirming to IS9103-1999 Reaffirmed -2008 (P.No.224/ I.No.28.7.15)	Cum	77.03	8000.00	Rupees Eight Thousand Only

	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri B P MAHESH	
				Rate	Rate in Words
6	KSRRB M300-53: Construction of embankment with approved material gravel/murrum with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement table 300-2 complete as per specifications. (which includes cost of gravel/murrum, watering charges & compaction by vibratory roller) MORTH specification No. 305, P No. 148/ Item No. 19.60	Cum	165.16	330.00	Rupees Three Hundred Thirty Only
7	KSRB 5.2.3 : Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.KBS 5.1.13 (Page No. 23/ Item No. 5.6)	Cum	21.00	4530.00	Rupees Four Thousand Five Hundred Thirty Only
8	KSRB 6-2.3 : Providing and constructing burnt brick masonry with approved quality of non-modular bricks of standard size of class designation 7.5 Newton per Sqmm with cement mortar 1:3 for basement and superstructure (machine moulded wirecut bricks) with cost of materials, labour charges, scaffolding, curing complete as per specifications. Specification No. KBS 6.2, (Page No. 27 / Item No. 6.11)	Cum	5.35	11500.00	Rupees Eleven Thousand Five Hundred Only
9	KSRB 4-1.7 : Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs with 20mm and down size graded granite metal coarse aggregate @ 0.84cum and fine aggregate @ 0.56 cum machine mixed concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications, specification. No. KBS 4.1,4.2.(P No.13 / Item No.4.7)	Cum	10.50	6000.00	Rupees Six Thousand Only
10	KSRB 15-3.10 : Providing 15mm thick cement plaster in single coat with cement mortar 1:3, to Brick masonry including rounding off corners wherever required smooth rendering, Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications (Page No.113 /Item No.15.12)	Sqm	8.91	300.00	Rupees Three Hundred Only

	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri B P MAHESH	
				Rate	Rate in Words
11	Providing and laying cement concrete using 20mm and down size granite jelly of ready mixed concrete **(RMC)** M20 for R.C.C works laid in 15cms thick layers and well compacted vibrating, curing, for raft foundation, column footing, main and secondary beams with all lead and lifts etc.,complete (exclusive of cost of steel and fabrication charges.)Page No.18/Item No.4.49.3)-do- M30	Cum	12.08	6900.00	Rupees Six Thousand Nine Hundred Only
12	Solid slab super structure KSRRB M2300-3.1 : Furnishing and placing reinforced / prestressed cement concrete in super-structure as per drawings and technical specification complete as per specification. B.RCC with OPC Cement design mix M25 @340kgs, with 20mm and down size graded granite metal,coarse aggregates @ 0.70cum ,and fine aggregated @ 0.47cum, with superplastisiser @ 3lts confirming to IS9103-1999 Reaffirmed -2008 case.I Using Concrete Mixer MORTH Specification No.1500, 1600 & 1700 height upto 5 mtr (P.No.229/ I.No.29.5)	Cum	75.06	8100.00	Rupees Eight Thousand One Hundred Only
13	KSRB 4.9.2: Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 -do- TMT Bars Fe 550 P.17/It.No.4.46.3	Tonne	21.1101	80000.00	Rupees Eighty Thousand Only
14	KSRB 4-6.5 : Providing and removing centering, shuttering, strutting, propping etc., for columns, pillars, piers, abutments, post and struts, square / rectangular / polygon in plan including cost of all materials, labour complete as per specifications. Specification NO KBS 4.6. (Page No. 16/ Item No. 4.32)	Sqm	119.52	400.00	Rupees Four Hundred Only
15	KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for **vertical surface** such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specifications. Specification NO KBS 4.6.2 (Page No. 15 / Item No. 4.31)	Sqm	388.32	320.00	Rupees Three Hundred Twenty Only

	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri B P MAHESH	
				Rate	Rate in Words
16	Providing and Laying flooring using prepolished water cut/gang saw m thick polished tandur blue stone slabs using cement mortar 1:6, 25mm thick over existing cement concrete bed or top of roof laid to line and level and jointed with cement slurry mixed with pigment to match the shade of the slab including cost of materials, labour, curing polishing complete as per specifications specifications No.KBS (Page No.103 / Item No.14.15)	Sqm	496.00	1299.00	Rupees One Thousand Two Hundred Ninety Nine Only
17	Providing and fixing for flooring 20mm thick gang saw water cut sadarhalli grey granite in CM 1:4 proportion, cut to required shape pattern with paper joints finished with cement mortar using white cement colour pigment to match colour of slab making through jointing with sealent, grooves in joints including cost of all materials mortar and labour etc.,complete as per specifications -do- minimum width of 1200mm (Page No.109 / Item No.14.61.1)	Sqm	264.82	2200.00	Rupees Two Thousand Two Hundred Only
18	KSRB 4-6.2 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for flat surface such as suspended floors, roofs, landings, balconies and likes, thickness upto 200 mm including cost of all materials, labour complete as per specifications. Specification NO KBS 4.6.2 (Page No. 15/ Item No. 4.18)	Sqm	428.91	420.00	Rupees Four Hundred Twenty Only
19	KSRB 15.3.13 : Providing **12mm thick cement plaster in single coat** with cement mortar 1:3, to ceiling including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications (Page No. 114/ Item No. 15.21)	Sqm	775.41	215.00	Rupees Two Hundred Fifteen Only
20	KSRB 15-3.10 : Providing 20mm thick cement plaster in single coat with cement mortar 1:3, to Stone masonry & concrete surface including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, cost of materials, labour, curingetc.,complete as per specifications (Page No.114/Item No.15.18)	Sqm	147.00	300.00	Rupees Three Hundred Only

B.P. Mahesh
Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.

Executive Engineer
Yelahanka Division
BBMP
Bruhat Bangalore Mahanagara Palike
BANGALORE - 560064